



## **Scope of Work**

### **Background:**

GRTC Transit Systems is constructing a Downtown Bus Transfer Center at 808 E. Clay Street on the old City courts parking lot. Construction is approximately 85% complete with bus Operations currently scheduled to begin on June 18, 2023. Operations start date is pending project completion. Restroom installation will be delayed until approx. the second week of July pending delivery and installation of the portable restrooms. It is anticipated GRTC will need to provide porta-potties as temporary until the restrooms are installed. Use of the transfer center will be from 5:30am — 1:30am on weekdays with reduced hours on weekends.

### **Scope of Work:**

- GRTC has contracted for purchase and manufacture of a portable restroom (like trailer type portable restrooms) with delivery expected second week of July 2023. Refer to the attached images of the restroom, floor plan, and features. The Comac Corporation, Inc. NIU CBOX20 ADA unit is the selected restroom to be installed within the site's property lines at the corner of Leigh Street and 8<sup>th</sup> Street. Restrooms are for GRTC bus Operators only. Not for public use.
- Employee card-readers will control access. Exterior lighting and cameras will also be installed. The restrooms have single-occupancy Men & Women's restrooms separated by a centrally located mechanical room containing a 300gal wastewater tank and a 200gal freshwater tank plus stainless-steel fixtures, touchless hand dryers and soap dispensers, and typical ADA features.
- Pumping 300gal wastewater tank every two days or three days depending on use.
- Providing fresh water to the 200gal freshwater tank every two or three days depending on use.